

C1. Detailed Design - Introduction

With the conceptual and preliminary design complete this section now looks at the detailed design requirements. This starts by detailed determination of loads including self weight, construction live load, in service live load and wind load. While this part may be very “elementary” there are some important issues that need to be appreciated concerning the characteristics of construction live loads and the application of various live load reduction factors. Using the detailed loading information, the various structural members are then checked against code requirements with the primary focus being on the detailed design of the erection columns, the composite beams, composite slab and connections. Consideration is also given to design of the shear core.

To understand the design of composite beams it is critical to appreciate that these beams must be designed for (at least) three fundamentally different configurations during their “life cycle” as discussed in section B4. AS2327.1 actually defines 7 different stages at which the beams should be checked but generally only three of these are critical as illustrated on the following page. At Stage 1, the beams are lightly loaded but unrestrained against beam buckling. At Stage 3, the beams carry the weight of the freshly poured concrete without the advantage of composite action. Only in the final Stage 7 when the building is complete, do the beams act compositely with the slab to support the in service loads.

Composite slabs must also generally be designed for three different stages or configurations. At the “wet concrete” stage, the decking must span between its supports (just like roof sheeting) to support the weight of the fresh concrete and the construction live load. (This is the stage that sets the maximum slab span as previously determined.) Once the concrete has gained strength then in the second “service” stage, the decking and concrete will act compositely to resist the service live loads. At this stage the decking effectively represents external bottom reinforcement to the slab. The third stage relates to performance of the slab during a fire event when the decking heats up and loses strength effectively leading to a situation where there is potentially no bottom reinforcement in the slab.

For both the beams and the slab, any one of the three potentially critical stages, may be the governing stage for the design.



C2. Design Stages and Construction Loading

- Refer to AS2327.1 Section 4 and Appendix F for definition of 'construction stages' and associated construction loads. These loads closely parallel those specified in AS3610 "Formwork for Concrete" but there are some significant differences because of the characteristics of composite decking systems and particularly the large loaded areas for the supporting beams and columns compared to relatively small supported areas with conventional formwork bearers, joists and props.
- Refer to Clause 4.4.2.4 of the Formwork code AS3610. This recommends designing formwork (prior to pouring concrete) for a 'stacked material load' of 4 kPa factored as a live load – but with no live load reduction - and in combination with the 1 kPa normal construction live load. This high loading is generally not critical for 'normal' formwork because of the higher slab thicknesses for which such formwork must be designed. In this application (with a 120 slab thickness), both the Bondek and its supporting beams at construction stage 3 defined below must be regarded as formwork. If the 4 kPa stacked material live load is applied, this heavy loading is likely to become a critical design case, requiring large and uneconomic steel beams. AS3610 does allow the 'stacked material load' to be deleted from design consideration, provided the allowable loading limits are clearly indicated on drawings and are enforced on site. This design is based only on the 1 kPa construction loading without the additional 4 kPa stacked materials load.

Stage	Description and assumptions	<u>Loading on supporting steel structure</u>
	* Stages 1, 3 and 7 are generally most critical	Local sheeting loads not considered refer AS2327.1 Sect. 4 and App. F.
0	Steel framework only	Self weight only
1*	Steel framework with formwork (profiled decking) in place. Assume the decking has minimal connection to the steel beams that will be unrestrained against beam buckling. (*Critical stages are shaded)	Self weight plus A 10 kN point load (at mid span) applied to the top flange of the steel beam OR $Q = 0.5 \text{ kPa for } A < 23 \text{ m}^2,$ $Q = 0.5 - [(A - 23) / 23] \times 0.2 \text{ kPa}$ for $A = 23 \text{ to } 46 \text{ m}^2$ $Q = 0.3 \text{ kPa for } A > 46 \text{ m}^2$
2	Shear studs and reinforcement installed. Assume shear studs are site welded through decking so that the beam top flanges are now continuously restrained against beam buckling. Particular design attention regarding beam stability is essential if studs are welded off site.	As for construction stage 1 plus the reinforcement – typically allow 0.1 kPa per 100 mm of slab thickness. (ie 0.12 kPa)
3*	Placing and finishing the fresh concrete. Again particular design attention to beam stability is required if studs are not welded through the decking.	Self weight plus $Q = 1.0 \text{ kPa for } A < 23 \text{ m}^2,$ $Q = 1.0 - [(A - 23) / 23] \times 0.4 \text{ kPa}$ for $A = 23 \text{ to } 46 \text{ m}^2$ $Q = 0.6 \text{ kPa for } A > 46 \text{ m}^2$
4	Concrete curing until concrete strength reaches 15 MPa (generally 7 days). No design implications provided the slab is protected from significant load changes.	The structure should support only self weight during this curing period.
5	Concrete curing until concrete strength reaches full design 28 day strength (generally another 7 days). No design implications during this time.	Self weight plus $Q = 1 \text{ kPa}$ with live load reduction as above Note that there is no propping.
6	From completion of curing until the end of construction and the commencement of the in service condition.	Note that during this time the superimposed dead load will be installed (partitions and services) in addition to a construction live load of 1 kPa.
7*	In service condition with the building complete – refer to following page	Self weight + superimposed dead load + design live loads (2.5, 3, 4 and 7.5 kPa).

Additional loading information is provided in AS2327.1 Appendix F relevant to 'local' patches of distributed load (due to stacked materials and the like) for which the steel decking must be designed. These small patches of load generally do not affect the design of the supporting steel beams.



Composite Design Example for Multistorey Steel Framed Buildings

Copyright © 2007 by AUSTRALIAN STEEL INSTITUTE

Published by: AUSTRALIAN STEEL INSTITUTE

All rights reserved. This book or any part thereof must not be reproduced in any form without the written permission of Australian Steel Institute.

Note to commercial software developers: Copyright of the information contained within this publication is held by Australian Steel Institute (ASI). Written permission must be obtained from ASI for the use of any information contained herein which is subsequently used in any commercially available software package.

FIRST EDITION 2007 (LIMIT STATES)

National Library of Australia Cataloguing-in-Publication entry:

Durack, J.A. (Connell Wagner)

Kilmister, M. (Connell Wagner)

Composite Design Example for Multistorey Steel Framed Buildings

1st ed.

Bibliography.

ISBN 978-1-921476-02-0

1. Steel, Structural—Standards - Australia.
2. Steel, Structural—Specifications - Australia.
3. Composite, (Engineering)—Design and construction.
 - I. Connell Wagner
 - II. Australian Steel Institute.
 - III. Title

Disclaimer: The information presented by the Australian Steel Institute in this publication has been prepared for general information only and does not in any way constitute recommendations or professional advice. The design examples contained in this publication have been developed for educational purposes and designed to demonstrate concepts. These materials may therefore rely on unstated assumptions or omit or simplify information. While every effort has been made and all reasonable care taken to ensure the accuracy of the information contained in this publication, this information should not be used or relied upon for any specific application without investigation and verification as to its accuracy, suitability and applicability by a competent professional person in this regard. Any reference to a proprietary product is not intended to suggest it is more or less superior to any other product but is used for demonstration purposes only. The Australian Steel Institute, its officers and employees and the authors, contributors and editors of this publication do not give any warranties or make any representations in relation to the information provided herein and to the extent permitted by law (a) will not be held liable or responsible in any way; and (b) expressly disclaim any liability or responsibility whatsoever for any loss or damage costs or expenses incurred in connection with this publication by any person, whether that person is the purchaser of this publication or not. Without limitation, this includes loss, damage, costs and expenses incurred as a result of the negligence of the authors, contributors, editors or publishers.

The information in this publication should not be relied upon as a substitute for independent due diligence, professional or legal advice and in this regards the services of a competent professional person or persons should be sought.



Table of contents

Table of contents	iii
Preface	v
Section A: INPUT INFORMATION	1
A1. Client and Architectural Requirements	2
A2. Site Characteristics	4
A3. Statutory Requirements	5
A4. Serviceability	8
A5. Design Loads	9
A6. Materials and Systems	10
A7. Design Aids and Codes	11
Section B: CONCEPTUAL AND PRELIMINARY DESIGN	12
B1. Conceptual and Preliminary Design	13
B1.1 Consideration of alternative floor framing systems– Scheme A	14
B1.2 Consideration of alternative floor framing systems– Scheme B	15
B1.3 Framing system for horizontal loading – initial distribution of load	16
B1.4 Alternatives for overall distribution of horizontal load to ground	17
B2. Preliminary Slab Design	21
B3. From Alternatives to Adopted Systems	22
B3.1 Adopted floor framing arrangement	22
B3.2 Adopted framing arrangement for horizontal loading	23
B4. Indicative Construction Sequence and Stages	24
B4.1 The importance of construction stages in composite design	24
B4.1 Indicative construction sequence and construction stages	25
B4.2 Adopted construction sequence for design of erection columns	27
B4.3 Core construction alternatives	27
B4.4 Adopted construction method for the core	27
B5. Preliminary Sizing of Primary and Secondary Beams	28
B6. Plenum Requirements and Floor to Floor Height	30
B7. Preliminary Column Sizes and Core Wall Thickness	33
Section C: DETAILED DESIGN	35
C1. Detailed Design - Introduction	36
C2. Design Stages and Construction Loading	37
C3. Detailed Load Estimation After Completion of Construction	38
C3.1 Vertical loading	38
C3.2 Wind loading	39
C3.3 Seismic loading Not considered	40
C4. Erection Column Design	41
C4.1 Load distribution for erection column design	42
C4.2 Side Column C5 (typical of C5 to C10)	43
C4.3 End column C2 (typical of C2, C3, C12 and C13)	44
C4.4 Corner column C1 (typical of columns C1, C4, C11 and C14)	44
C5. Floor Beams – Construction Stage 1	45
C5.1 Secondary beams Group S1(11 050, 2800) (Beams B22 – B41, B43 – 48)	45
C5.2 Primary beams Group P1(9800, 5725) (Beams B1, B7 to B12, B18,	46
B19 – 21, B49 – 51 and B42)	46
C5.3 Primary beams Group P2(9250, 6600) (B2, B6, B13 and B17)	47
C6. Floor Beams – Construction Stage 3	48
C6.1 Secondary beams Group S1(11 050, 2800) (Beams B22 – 41, B43 – 48)	48
C6.2 Primary beams Group P1(9800, 5725) (Beams B1, B7 - B12, B18 – 21,	49
B49 – 51 and B42)	49
C6.3 Primary beams Group P2(9250, 6600) (Beams B2, B6, B13, B17)	49
C7 Floor Beam Design for Occupancy Loading	50
C7.1 Secondary beams Group S1(11 050, 2800) (Beams B19, B21, B22 - B41,	51
B43 – B49 and B51)	51



C7.2	Primary beams Group P1(9800,5725) (Beams B1, B7 to B12, B18)	58
C7.3	Primary beams group P2(9050, 6600) (Beams B2, B6, B13, B17)	63
C8.	Assessment of Dynamic Performance of Floor System	69
C8.1	Definition of the dynamic assessment process	69
C8.2	Application of the dynamic assessment process	73
C9	Final Slab Design	79
C9.1	Slab design for the office areas	79
C9.2	Slab design for the compactus areas	80
C10.	Longitudinal Shear Reinforcement Design	81
C10.1	Introduction	81
C10.2	Proprietary longitudinal shear reinforcement products	83
C10.3	Secondary beams group S1, B22 typical – longitudinal shear design	84
C10.4	Internal primary beams group P2, (B2 typical) longitudinal shear design	85
C10.5	Primary beams P1, (B1 typical) – longitudinal shear design	87
C10.6	Perimeter beams B19 to 21 and B49 to 51	88
C11.	Floor System Design Review and Final Decisions	89
C11.1	Floor design review	89
C11.2	Final floor framing plan and deck reinforcement	90
C12.	Final Design of RC Columns	91
C13.	Detailed Design of the Core	91
C13.1	Preliminary discussion and statement of limitations of this section	91
C13.2	Basic modelling of the core using beam elements	92
C13.3	The Space Gass Analysis Model	96
C13.4	Model verification and static deflections for W_s	97
C13.5	Dynamic analysis for natural frequency of building	98
C13.6	Interpretation and application of stress resultants from Space Gass	100
C13.7	Further investigation of the core using a Strand7 finite element model	102
C13.8	Review of core investigations	105
C14.	Steel Connection Design	106
C14.1	Can it be built?	106
C14.2	Representative connections	108
C14.3	Web side plate connection design for $V^* = 142$ kN	108
C14.4	Flexible end plate connection for $V^* = 279$ kN	112
C14.5	B2 to core web side plate connection for $V^* = 308$ kN	113
C14.6	Column splice for a load of $N^* = 1770$ kN	114
C14.7	Column base plate for a load of $N^* = 1770$ kN	115
C15.	Web Penetrations	116
C16.	Some Final Thoughts and Disclaimers	117
Appendix I	Theory and discussion – composite slabs	119
Appendix II	Theory and discussion - composite beams	133
Appendix III	Dynamic assessment of the floor system	149
Appendix IV	Theory and discussion steel connections	163
Appendix V	Corrosion and fire protection	175

